



Republic of the Philippines
Department of Education
REGION IV-A CALABARZON
SCHOOLS DIVISION OF BATANGAS

REQUEST FOR QUOTATION

November 26, 2023

The DepEd Division of Batangas, through the General Appropriations Act (GAA) FY 2023 intends to apply the sum of Nine Hundred Ninety-Seven Thousand , Nine Hundred Two pesos and 94/100 only (₱997,902.94) being the Approved Budget for the Contract (ABC) to payments under the contract **PR No. 2023-11-0131** 'Supply, Delivery and Installation of Access points and PTZ Cameras in the Division Office

Unit	Item Description	Quantity
lot	LOT 'Supply, Delivery and Installation of Access points and PTZ Cameras in the Division Office (see attached Program of Works)	1
	Delivery Period: 45 Calendar Days	:

Other Information

Interested suppliers must submit their valid and current Mayors Permit, PhilGEPS Registration, Income Business Tax Return/ Tax Clearance Omnibus Sworn Statement, and Price Quotation.

Submission of quotation and eligible documents (2 copies) in a sealed envelope, and/or courier duly signed by your authorized representative is on or before November 30, 2023, at 10:00 AM at BAC Office, DepEd Division of Batangas. The signed quotation must be addressed to Mr. Nicolas M. Burgos, BAC Chairperson DepEd Division of Batangas Province, Provincial Sports Complex, Batangas City

For inquiries, you may contact us at Tel. Nos. (043) 723-1796: (043) 722-1437.

The DepEd Batangas reserves the right to accept or reject any bid, to annul the bidding process, and to reject all bids at any time prior to contract award, without incurring any liability to the affected bidder or bidders.

For further information, please refer to:

RODRIGO S. CASTILLO, Ed.D.

BAC Secretariat
DepEd Batangas
Provincial Sports Complex
Bolbok, Batangas City
043-722-1437

NICOLAS M. BURGOS

Chairperson, Bids and Awards Committee



Address: Provincial Sports Complex, Bolbok, 4200 Batangas City
☎(043)722-1840 / 722-1796 / 722-1437 / 722-2675 / 722-1662
✉deped.batangas@deped.gov.ph
🌐www.depedbatangas.com

PROGRAM OF WORKS

DETAILED COST ESTIMATE

Supply, Delivery and Installation of Access points and PTZ Cameras in the Division Office

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL PRICE
GENERAL REQUIREMENTS					
1	Mobilization/Temporary Structures, Utilities and Services/Demobilization	1	lot		
2	Safety and Health	1	lot		
	Sub Total				
	Tax 5% of (I + II)				
	TOTAL (I + II + III)				
A. CABLING MATERIALS					
1	CAT6 UTP Cable 300m	4	box		
2	Cat 6 24Ports Patch Panel	3	Unit		
3	Cable Manager 1RU	3	pc		
4	Wiring Accessories	1	lot		
	Sub Total of Material Cost				
	Indirect Cost 22% of (I)				
	Tax 5% of (I + II)				
	TOTAL (I + II + III)				
B. ADDITIONAL NETWORK INFRASTRUCTURE ACCESS POINT AND PTZ CAMERA					
1	Load Balancing Router RAM: 128 MB DDR3 WAN Ports: 2 x 10/100/1000 Base-T Power supply: 100~240V AC	1	Unit		
2	Gigabit Wireless Access Point (Outdoor) Wireless Protocol:Wi-Fi 6 Port: 2 x 10/100/1000 Base-T MIMO: 2.4 GHz and 5 GHz Power Supply: 802.3at PoE	1	Unit		
3	Gigabit Wireless Access Point (ceiling type) Wireless Protocol:802.11ax (Wi-Fi 6), 1775Mbps Port:2 x 10/100/1000 Base-T MIMO: 2.4 GHz and 5 GHz Power Supply: 802.3at PoE	9	Unit		
4	Gigabit 16 Ports POE Switch Hub Cloud Managed Ports:16 x 10/100/1000Base-T PoE+ ports, 2 SFP uplink POE: 240W, IEEE 802.3at / IEEE 802.3af Fan: Built in	1	Unit		
5	Gigabit 8 Ports POE Switch Hub Cloud Managed 8 x 10 x 10/100/1000Base-T PoE+ ports PoE: IEEE 802.3at / IEEE 802.3af	1	Unit		

6	Uninterruptible Power Supply Rack Type 2KVA	3	Unit		
7	IP PTZ Camera 25x optical zoom 2Megapixel	2	pcs		
	Sub Total of Material Cost				
	Indirect Cost 22% of (I)				
	Tax 5% of (I + II)				
	TOTAL (I + II + III)				
C. ROUGHING-IN MATERIALS					
1	PVC Pipe 1/2"	35	pcs		
2	PVC Pipe 3/4"	35	pcs		
3	PVC Pipe 1"	30	pcs		
4	PVC Adaptor w/ locknut 1/2"	30	pcs		
5	PVC Adaptor w/ locknut 3/4"	30	pcs		
6	PVC Adaptor w/ locknut 1"	30	pcs		
7	PVC Elbow 1/2"	10	pcs		
8	PVC Elbow 3/4"	8	pcs		
9	PVC Elbow 1"	8	pcs		
10	Full Threaded Round Bar	2	pcs		
11	Anchor Bolt 3/8"	50	pcs		
12	Hexagonal Nut 3/8"	50	pcs		
13	Washer 3/8"	50	pcs		
14	Pipe Hanger 1/2"	30	pcs		
15	Pipe Hanger 3/4"	30	pcs		
16	Pipe Hanger 1"	30	pcs		
17	Junction Box w/ cover	20	pcs		
18	Square Box 2x4x4 w/ cover	10	pcs		
19	Pull Box 6x6x4	2	pcs		
20	Pull Box 8x8x4	2	pcs		
21	Plastic tox #6 (100pcs)	1	pack		
22	Metal Screw #6 (100pcs)	1	pack		
23	Cable Tie #8	1	pack		
24	Cable Tie #10	1	pack		
25	Masking Tape 3/4"	2	pcs		
26	Electrical Tape	4	pcs		
27	Guide Wire	3	kl		
28	Restoration	1	lot		
29	Support and roughing-in accessories	1	pcs		
	Sub Total of Material Cost				
	Indirect Cost 22% of (I)				
	Tax 5% of (I + II)				
	TOTAL (I + II + III)				
D. INSTALLATION SERVICES					
1	Installation of Cat6 UTP Cable				
2	Installation of Load Balancing Router				

3	Installation of Cat6 24 Ports Patch Panel				
4	Installation of 1RU Cable Manager				
5	Installation of Gigabit Wireless Access Point (Outdoor)				
6	Installation of Gigabit Wireless Access Point (ceiling type)				
7	Installation of Patch Cord Slim Type 2 mtrs Cat6				
8	Installation of Gigabit 16 Ports POE Switch Hub Cloud Managed	1	lot		
9	Installation of Gigabit 8 Ports POE Switch Hub Cloud Managed				
10	Installation of 2KVA Rack Type UPS				
11	Installation of IP PTZ Camera				
12	Cable Termination in Patch Panel				
14	Line to Line Testing				
15	Documentation				
16	As-built Plan and Project Turn-Over				
	Sub Total of Material Cost				
	Indirect Cost 22% of (I)				
	Tax 5% of (I + II)				
	TOTAL (I + II + III)				
	GRAND TOTAL				

Delivery Period

45 CD